

**THE CORPORATION OF THE CITY OF MISSISSAUGA
BUILDING BY-LAW**

SCHEDULE "D"

PREScribed NOTICES / INSPECTIONS

PRESCRIBED NOTICES / INSPECTIONS	
Notice / Inspection	Description
Footing	Readiness to construct footings.
Backfill	Substantial completion of footings and foundations prior to commencement of backfilling.
Framing	Substantial completion of structural framing.
HVAC Rough-In	Substantial completion of ductwork and piping for heating and air conditioning systems, and air-contaminant extraction equipment if applicable.
Insulation	Substantial completion of insulation and vapour barriers. Substantial completion of air barrier systems.
Fire Separations	Substantial completion of all required fire separations and closures.
Fire Protection Systems	Substantial completion of all fire protection systems including standpipe, sprinkler, fire alarm, and emergency lighting systems.
Fire Access Routes	Substantial completion of fire access routes.
Building Sewers	Readiness for inspection and testing of building sewers.
Building Drains	Readiness for inspection and testing of building drains.
Water Service Pipe	Readiness for inspection and testing of water service pipes.
Fire Service Main	Readiness for inspection and testing of fire service mains.
Plumbing Rough-in (DWV)	Readiness for inspection and testing of drainage systems and venting systems.
Plumbing Rough-in (Water Distribution)	Readiness for inspection and testing of the water distribution system.
Pool/Spa Suction and Gravity Outlet System	Readiness for inspection of suction and gravity outlets, covers and suction piping outlets of an outdoor pool described in Clause 1.3.1.1.(1)(j) of Division A, a public pool or spa.

SCHEDULE “D” (continued)

PRESCRIBED NOTICES / INSPECTIONS	
Notice / Inspection	Description
Pool/Spa Circulation/ Recirculation System	Substantial completion of the circulation/recirculation system of an outdoor pool as described in Clause 1.3.1.1.(1)(j) of Division A, a public pool or spa and substantial completion of the pool before it is filled with water.
Sewage System Excavation	Readiness to construct the sewage system.
Sewage System Completion	Substantial completion of the installation of the sewage system before the commencement of backfilling.
Site Services	Substantial completion of installation of plumbing not located in a structure before the commencement of backfilling.
Occupancy Permit (Unfinished Building)	Completion of construction and installation of components required to permit the issue of an occupancy permit under Sentence 1.3.3.1.(3) of Division C or to permit occupancy under Sentence 1.3.3.2.(1) of Division C, if the building or part of the building to be occupied is not fully completed.
	Completion of construction and installation of components required to permit the issue of an occupancy permit under Article 1.3.3.4. (4), 1.3.3.5.(3) or 1.3.3.7.(8) of Division C.
Final (Plumbing)	Readiness for inspection and testing of plumbing fixtures and plumbing appliances.
Final (HVAC)	Substantial completion of heating, ventilation, air-conditioning and air-contaminant extraction equipment.
Final (Completion of Occupied Building)	Completion of a building where a person has occupied or permitted the occupancy under Article 1.3.3.1 or 1.3.3.2. of Division C.
	Completion of a building for which an occupancy permit is required under Article 1.3.3.4., 1.3.3.5. or 1.3.3.7. of Division C.
Final (General)	Occupancy or use after completion of building.